

**BID ITEMS FOR THE CONSTRUCTION OF LONG BEACH WATER RECLAMATION PLANT
CONCRETE AND PROTECTIVE LINING REPAIR-PHASE II**

Item 1 – For the construction of Long Beach Water Reclamation Plant Concrete and Protective Lining Repair-Phase II, complete as shown and specified in the Contract Documents, but EXCLUDING the work described under Items 2 through 7 below, the lump sum of:

= \$ _____
(Figures)

Item 2 – For furnishing labor, material, and equipment to remove approximately 22,000 square feet of existing protective polyvinyl chloride lining system (adhesive mastic) on the concrete surfaces, including cleanup, and disposal, complete as shown and specified in the Contract Documents, the unit price of:

\$ _____ per sf x 22,000 = \$ _____
(Figures) (Total)

Item 3 – For furnishing labor, material, and equipment for surface preparation and installation of approximately 30,000 square feet of protective polyvinyl chloride lining system on concrete surfaces, but EXCLUDING the work described under Items 4 through 6 below, complete as shown and specified in the Contract Documents:

- (a) For preparation of approximately 30,000 square feet of concrete surface, including removal of deteriorated concrete, repair of deteriorated concrete surface areas with profile depressions less than or equal to 1-inch (including finishing and curing), cleanup and disposal, and other work incidental thereto, complete as shown and specified in the Contract Documents, the unit price of:

\$ _____ per sf x 30,000 = \$ _____
(Figures) (Subtotal)

- (b) For installation of approximately 30,000 square feet of protective polyvinyl chloride lining system, including application of primer, mastic, polyvinyl chloride lining material, inspection, curing and cleanup, and other work incidental thereto, complete as shown and specified in the Contract Documents, the unit price of:

\$ _____ per sf x 30,000 = \$ _____
(Figures) (Subtotal)

Total for Item 3 = \$ _____
(Total)

FOR ITEMS 4, 5, 6, AND 7 ONLY: The District reserves the right to use all or none or any portion of the bid items without renegotiation of the bid price. The bid price shall include all direct and non-direct costs.

**BID ITEMS FOR THE CONSTRUCTION OF LONG BEACH WATER RECLAMATION PLANT
CONCRETE AND PROTECTIVE LINING REPAIR-PHASE II**

Item 4 – For furnishing labor, material, and equipment to repair approximately 8,500 square feet of deteriorated concrete surface areas with profile depressions greater than 1-inch and less than or equal to 2-inches, including finishing and curing, final surface preparation, cleanup and other work incidental thereto, in addition to what is shown and specified in the Contract Documents, the unit price of:

\$ _____ per sf x 8,500 = \$ _____
(Figures) (Total)

Item 5 – For furnishing labor, material, and equipment for structural repair of approximately 2,500 square feet of deteriorated concrete surface areas where existing reinforcing steel has corroded away, with profile depressions greater than 2-inches and less than or equal to 4-inches, including reinforcing steel placement (maximum steel placement of 2 pounds per square foot), application of protective coating on exposed reinforcing steel, finishing and curing, final surface preparation, cleanup and other work incidental thereto, in addition to what is shown and specified in the Contract Documents, the unit price of:

\$ _____ per sf x 2,500 = \$ _____
(Figures) (Total)

Item 6 – For furnishing labor, material, and equipment for the installation of approximately 700 linear feet of contraction joint material, joint sealant and polyethylene backer rod in existing contraction joints, including cleanup and all other work incidental thereto, in addition to what is shown and specified in the Contract Documents, the unit price of:

\$ _____ per lf x 700 = \$ _____
(Figures) (Total)

Item 7 – For furnishing labor, material, and equipment to excavate, load, transport, and proper disposal off-site of approximately 100 cubic yards of unsuitable material under or adjacent to the construction area, and replacing with imported structural backfill or crushed aggregate base, including delivery, placement, compaction, grading, and all other work incidental thereto, in accordance with **Section 2B** of the Special Provisions and the Contract Documents, as directed by the Engineer and in addition to what is shown and specified in the Contract Documents, the unit price of:

\$ _____ per cy x 100 = \$ _____
(Figures) (Total)

**TOTAL OF BID ITEMS 1 THROUGH 7
FOR THE CONSTRUCTION OF
LONG BEACH WATER RECLAMATION PLANT
CONCRETE AND PROTECTIVE LINING REPAIR-PHASE II**

= \$ _____
(Figures, Total)

BID ITEMS AND TOTAL SHALL INCLUDE ALL APPLICABLE TAXES